

NOTES AND SPECIFICATIONS

1. ALL THE DIMENSIONS ARE IN MILLIMETRES AND THE LEVELS ARE IN METRES.
2. DO NOT SCALE THE DRAWING. ONLY FIGURED DIMENSIONS SHALL BE FOLLOWED.
3. THE SINGLE LANE ROAD BRIDGE IS DESIGNED FOR A CARRIAGE WAY WIDTH OF 4.25M AND FOR ONE LANE OF IRC CLASS 'A' LOADING.
4. THE BRIDGE IS DESIGNED ADOPTING THE FOLLOWING IRC AND IS CODES.

i. IRC - 5 - 1998

ii. IRC - 6 - 2000

iii. IRC - 21 - 2000

iv. IRC - 78 - 2000

v. IRC - 83 - 2000

vi. IS 456 - 2000

vii. IS 383
5. THE SPECIFICATIONS PROPOSED FOR THE VARIOUS COMPONENTS OF THE STRUCTURE ARE AS FOLLOWS:

Sl.No	DETAILS OF COMPONENTS	GRADE OF CONCRETE AS PER IRC: 6-2000	MAX. SIZE OF C.A AS PER IS:383
1	WEARING COAT OF SLAB	CC M30	20 MM
2	DECK SLAB	RCC M20	20 MM
3	BED BLOCK OVER ABUTMENT	RCC M25	20 MM
4	BEDBLOCK OVER PIER	RCC M25	20 MM
5	PIER	RCC M25	20 MM
6	ABUTMENT AND RETURN	CC M15	40 MM
7	PIER FOUNDATION	RCC M20	20 MM
8	ABUTMENT & RETURN FOUNDATION	CC M15	40 MM
9	APPROACH SLAB	CC M20	20 MM
10	LEVELLING COURSE FOR PIER LINING FOR CANAL	CC M10	40 MM
11		CC M10	20 MM

HYDRAULIC PARTICULARS

S.NO	DESCRIPTION OF ITEMS	QUANTITY & UNITS
1	DISCHARGE REQUIRED	4.89 CUMECS
2	DISCHARGE DESIGNED	4.95 CUMECS
3	BED WIDTH	4.50 M
4	FULL SUPPLY DEPTH	1.20 M
5	VELOCITY	0.65 M/SEC
6	BED FALL	1 / 3750
7	SIDE SLOPES ( HDR/ SOILS )	1.5 : 1
8	COEFFICIENT OF RUGOSITY	0.0225
9	CANAL BED LEVEL	+ 242.185 M
10	FULL SUPPLY LEVEL	+ 243.385 M
11	TOP OF BANK LEVEL	+ 243.985 M
12	EXSISTING ROAD LEVEL	+ 244.840M
13	PROPOSED ROAD LEVEL	+ 244.840 M
14	SKEW ANGLE	0 °


STRESS TABLE

S.NO	DESCRIPTION OF ITEMS	STRESSES IN T / SQ.M			
		IN CONCRETE		ON SOIL	
		MAX.	MIN.	MAX.	MIN.
1	PIER	96.43	(-) 51.01	11.56	0.17
2	ABUTMENT	23.81	(-) 5.75	16.82	0.34


REFERENCE DRAWINGS

1. DRAWING NO. SKD/SLRB/002/2008 - RCC DETAILS OF PIER, PIER FOOTING AND ABUTMENT


REVISION NO:	DRAWN	CHECKED	APPROVED	DATE
CLIENT	GOVERNMENT OF ANDHRA PRADESH IRRIGATION & CAD DEPARTMENT			
PROJECT	GANDIKOTA LIFT IRRIGATION SCHEME SANTHAKOVUR DISTRIBUTORY			
TITLE	SINGLE LANE ROAD BRIDGE AT KM. 8.130 GENERAL PLAN AND SECTIONS			
CONTRACTORS	M/S KBL - MCCL (JV) PUNE			
CONSULTANTS				
DRAWING NO:	SCALE		DATE	
SKD/SLRB/001/2008	AS INDICATED			



SECTIONAL ELEVATION 'A-A'




TRAIL PIT PARTICULARS @ KM 5.718




HALF PLAN AT TOP AND HALF PLAN AT BOTTOM

SCALE 1 : 100



SECTIONAL ELEVATION AT ' PP '

SCALE 1 : 50



SECTION OF ABUTMENT

SCALE 1 : 50

Sd/- 15-8-08  
SUPERINTENDING ENGINEER  
GNSS CIRCLE, KADAPA.