






R.C.C.DETAILS OF BOX UNDER EARTH BANK (2 VENTS OF 2,90 M X 1,2 M)












D/5 WING WALL & Return





- 1. ALL DIMENSIONS ARE IN MILLIMETRES AND LEVELS ARE IN METRES.FOLLOW FIGURED DIMENSIONS AND DO NOT SCALE THE DRAWING.
- 2. BACK FILLING SHALL BE DONE SIMULTANEOUSLY WITH THE RAISING OF THE WINGS & RETURNS USING SOILS WITH ANGLE OF REPOSE NOT LESS THAN 28° AND PERMEABILITY COEFFICIENT 'K' VALUE NOT MORE THAN 3M/YEAR.
- 3. THE MAXIMUM STRESSES ON FOUNDATION STRATA WORKED OUT FOR THE WINGS & RETURNS ARE SHOWN IN STRESS TABE. IF THE FOUNDATION STRATA METWITH DURING EXECUTION IS INFERIOR AND CANNOT TAKE THE DESIGNED STRESSES, THE SECTIONS ARE TO BE SUITABLY REVISED.
- 4. MINIMUM COVER TO ALL REINFORCEMENT SHALL BE 30 MM TO ENSURE PROPER COVER OF CONCRETE TO REINFORCEMENT.
- 5. ALL REINFORCING STEEL SHALL BE OF HIGH YIELD STRENGTH DEFORMED BARS, (FE 415) CONFORMING TO IS 1786 1985.
- 6. JOINTS OR LAPPING OF BARS IN MAIN REINFORCEMENT SHALL BE AVOIDED AS FAR AS POSSIBLE. HOWEVER IF LAPS ARE INEVITABLE, THE PROVISION IN CLAUSE 304.6.6 OF IRC 21 2000 SHALL BE STRICTLY FOLLOWED.
- 7. BENDING OF REINFORCEMENT BARS SHALL BE AS PER IS 2502. SUPPORTING CHAIRS OF 12 MM DIA SHALL BE PROVIDED AT SUITABLE INTERVALS AS PER IS 2502.
- 8. CONCRETE SHALL BE PREPARED IN THE MECHANICAL MIXERS OF CAPACITY NOT LESS THAN 200 LITRES. PROPER COMPACTION OF CONCRETE SHALL BE ENSURED BY USE OF FORM AND NEEDLE VIBRATORS.
- 9. ALL HAUNCHES PROPOSED IN THE BOXES ARE OF 100 X 100 SIZE

		STRESS TABLE					
				STRESSES IN T/SQ.M			
C No	PARTICULARS			IN CONCRETE		ON SOIL	
S.No.				MAX.	MIN.	MAX.	MIN.
1	U/S HEAD	U/S HEAD WALL		2.75	1.53	-	-
2	D/S HEAD	D/S HEAD WALL		1.35	1.19	-	_
3	U/S WING & Return WALL			9.86	1.54	8.08	3.67
4	D/S WING	D/S WING & Return WALL			1.15	7.25	3.32

S.NO.	PARTICULARS	GRADE OF CEMENT CONCRETE AS PER IS:456-2000	MAX SIZE OF GRADED COARSE AGGREGATE AS PER IS:383	
Α	APRON	CC M15 GRADE	40 MM	
В	WINGS, RETURNS, HEAD WALLS, DROP WALLS & FOUNDATIONS	CC M15 GRADE	40 MM	
С	WEARING COAT	CC M25 GRADE	20 MM	
D	SEALING COAT	CC M25 GRADE	20 MM	
Е	BOX	RCC M2O GRADE	20 MM	

## REFERENCE DRAWINGS

1. DRAWING NO. GLIS/MSC/UT-19.625/001/2010 - GENERAL PLAN AND SECTIONAL ELEVATION

REVISION NO:	DRAWN	CHECKED	APPROVED	DATE	
CLIENT	GOVERNMENT OF ANDHRA PRADESH IRRIGATION & CAD DEPARTMENT				
PROJECT	GANDIKOTA LIFT IRRIGATION SCHEME MALYALA SUPPLY CHANNEL				
111111111111111111111111111111111111111	UNDER TUNNEL AT KM. 19.625 RCC DETAILS OF BOX				
CONTRACTORS	KBL - I HYDER	MCCL (JV) ABAD			
DRAWING NO:		SCALE		DATE	
GLISS/MSC/UT/ 19.625/002/2010	AS INDICATED				